

**FY 2008 TRANSPORTATION CAPITAL PROGRAM
New Jersey Department of Transportation Projects**

| | |
|--|--------------------------|
| PROGRAM/PROJECT NAME | Project ID Number |
| Sussex County Route 605 Connector | NS9911 |

The county will investigate alternatives for connecting CR 605 to Route 206/183.

The following special Federal appropriation was allocated to this project. FY06 SAFETEA-LU, HPP, \$800,000 (available 20% per year).

COUNTY: Sussex

MUNICIPALITY: Byram Twp. Stanhope Boro Hopatcong Boro

MILEPOSTS: N/A

STRUCTURE NO.: N/A

LEGISLATIVE DISTRICT: 24

SPONSOR: Sussex County

PROGRAM CATEGORY: Local Aid - Local Roadway Improvements

| MPO | Phase | Fund | Amount |
|------------|--------------|-------------|---------------|
| NJTPA | LPD | HPP20 | \$640,000 |

**FY 2008 TRANSPORTATION CAPITAL PROGRAM
New Jersey Department of Transportation Projects**

| | |
|---|--------------------------|
| PROGRAM/PROJECT NAME | Project ID Number |
| Route 23, Hardyston Twp., Silver Grove Road to Holland Mountain Road | 96039 |

Safety and drainage improvements within three sections of Rt. 23 in Hardyston Township, Sussex County totaling approximately 2.2 miles of Route 23. The sections are: "Northern/Laceytown Road section" in the vicinity of the Rt. 23 and Laceytown Road intersection, milepost 30.6 to 31.22; "Holland Mountain Road section", in the vicinity of the Holland Mountain Road intersection. Improvements in the vicinity of milepost 30.9 will include the addition of shoulders as well as improving the horizontal alignment by straightening the reverse curves. In the vicinity of Lake Shore Road, improvements will include a two-way, left-turn lane and shoulder in each direction, with left-turn slots for turning movements to Lake Shore Road. At the request of the Township the left-turn lane will be extended to East Shore Trail. In the vicinity of Holland Mountain Road, Snufftown Road will be realigned to form a four-way, signalized intersection with Route 23 and Holland Mountain Road. The alignment will be upgraded to provide shoulder and adequate vertical sight distance and a left-turn slot will be provided for access to Holland Mountain Road and Snufftown Road as well as a two-way, left-turn lane. The Pacock Brook culvert will also be replaced. This project will be bicycle/pedestrian compatible. This project is multi-year funded under the provisions of Section 13 of P.L. 1995, c.108. Total Federal aid needed is anticipated to be \$38.502 million for construction.

The following special Federal appropriation was allocated to this project. FY06 SAFETEA-LU, HPP \$3,440,000 (available 20% per year).

COUNTY: Sussex

MUNICIPALITY: Hardyston Twp. Franklin Boro

MILEPOSTS: 26.80 - 31.80

STRUCTURE NO.: 1903150 1903153

LEGISLATIVE DISTRICT: 24

SPONSOR: NJDOT

PROGRAM CATEGORY: Roadway Preservation - Hwy Rehab and Recon

| MPO | Phase | Fund | Amount |
|-------|-------|-------|-------------|
| NJTPA | ROW | DEMO | \$998,000 |
| NJTPA | ROW | HPP20 | \$2,752,000 |

**FY 2008 TRANSPORTATION CAPITAL PROGRAM
New Jersey Department of Transportation Projects**

| | |
|--|--------------------------|
| PROGRAM/PROJECT NAME | Project ID Number |
| Route 80, Eastbound, West of Hope-Johnsonburg Road to East of Ledgewood Avenue, Resurfacing | 06410 |

The existing roadway typically consists of three to four 12-foot asphalt concrete travel lanes with 12-foot asphalt concrete shoulders. The opposing traffic is separated by a woods and a grass median. The roadway condition is generally poor, consistently exhibiting rutting, high severity wheel path fatigue cracking, and localized patching. The outside shoulder is generally in fair to poor condition. It is proposed to mill and resurface the entire roadway with Superpave hot mix asphalt. All inlets and other roadway utility hardware will be adjusted to final grade. Raised pavement markers will be reinstalled. Deteriorated curb and curb with existing low reveal will be reconstructed. No utility work is anticipated. Only resurfacing and incidentals required to facilitate the resurfacing as outlined in the scope of work for 3R projects will be done.

Bridge decks within the project limits do not require rehabilitation; therefore, pavement will be transitioned to meet the bridge decks. A minimum vertical under clearance of 16 feet will be maintained at all underpasses with the exception of Structure 1427150 which will be at 15 feet, 8 inches.

COUNTY: Warren Sussex Morris
MUNICIPALITY: Various
MILEPOSTS: 12.80 - 28.50
STRUCTURE NO.: N/A
LEGISLATIVE DISTRICT: 23 24 25 **SPONSOR:** NJDOT
PROGRAM CATEGORY: Roadway Preservation - Highway Resurfacing

| MPO | Phase | Fund | Amount |
|-------|-------|-------|--------|
| NJTPA | CON | STATE | |

**FY 2008 TRANSPORTATION CAPITAL PROGRAM
New Jersey Department of Transportation Projects**

| | |
|--|--------------------------|
| PROGRAM/PROJECT NAME | Project ID Number |
| Route 80, Westbound, West of Hope-Johnsonburg Road to East of Ledgewood Avenue, Resurfacing | 06411 |

The existing roadway typically consists of three to four 12-foot asphalt concrete travel lanes with 12-foot asphalt concrete shoulders. The opposing traffic is separated by a woods and a grass median. The roadway condition is generally poor, consistently exhibiting rutting, high severity wheel path fatigue cracking, and localized patching. The outside shoulder is generally in fair to poor condition. It is proposed to mill and resurface the entire roadway with Superpave hot mix asphalt. All inlets and other roadway utility hardware will be adjusted to final grade. Raised pavement markers will be reinstalled. Deteriorated curb and curb with existing low reveal will be reconstructed. No utility work is anticipated. Only resurfacing and incidentals required to facilitate the resurfacing as outlined in the scope of work for 3R projects will be done.

Bridge decks within the project limits do not require rehabilitation with the exception of Structure 1427154; therefore, pavement will be transitioned to meet the bridge decks. A minimum vertical under clearance of 16 feet will be maintained at all underpasses with the exception of Structure 1427150 which will be at 15 feet, 8 inches.

COUNTY: Warren Sussex Morris

MUNICIPALITY: Various

MILEPOSTS: 12.80 - 28.50

STRUCTURE NO.: N/A

LEGISLATIVE DISTRICT: 23 24 25 **SPONSOR:** NJDOT

PROGRAM CATEGORY: Roadway Preservation - Highway Resurfacing

| MPO | Phase | Fund | Amount |
|------------|--------------|-------------|---------------|
| NJTPA | CON | STATE | |