

**FY 2014 TRANSPORTATION CAPITAL PROGRAM  
New Jersey Department of Transportation Projects**

<i>Program/Project Name</i>	<i>Item # 77</i>	<i>Project ID Number: 08316</i>
<b>Route 9, Bridge over Waretown Creek</b>		

This project will replace the 82-year old two span structure over Waretown Creek. The existing deck and superstructure are both rated poor. The existing center pier exhibits numerous vertical cracks, which extend from the top of the pier down below the waterline.

**COUNTY:** Ocean

**MUNICIPALITY:** Ocean Twp

**MILEPOSTS:** 78.29

**STRUCTURE NO.:** 1502152

**LEGISLATIVE DISTRICT:** 9

**SPONSOR:** NJDOT

**CIS PROGRAM CATEGORY:** Bridge Assets

**CORE MISSION:** State of Good Repair and Safety (10)

<b>MPO</b>	<b>Phase</b>	<b>Fund</b>	<b>Amount</b>
NJTPA	DES	NHPP	\$600,000

**FY 2014 TRANSPORTATION CAPITAL PROGRAM  
New Jersey Department of Transportation Projects**

<i>Program/Project Name</i>	<i>Item # 78</i>	<i>Project ID Number: 97071</i>
<b>Route 9, Craig Road/East Freehold Road, Intersection Improvements</b>		

On the Rt. 9 and Craig Road intersection, it is proposed to add an additional lane in each direction. The majority of the widening will be in the existing grass median. A concrete barrier will be installed for safety. A reverse-loop jug handle for Rt. 9 northbound is proposed on the northern side of the Getty gas station. A deceleration lane for the jug handle will begin in advance of the traffic signal. Right and left turns will be permitted from the jug handle onto Pond Road. Rt. 9 northbound traffic destined for Pond Road southbound will continue to use the existing ramp which will be restricted to right turns. The Access Design unit has granted a waiver for cars and smaller trucks only, with ingress to the Getty gas station from the deceleration lane on Rt. 9 northbound. All vehicles will exit from the rear of the gas station onto Pond Road.

A traffic signal is proposed at the intersection of Craig/East Freehold Road and Pond Road. The signal will be coordinated with the Rt. 9 traffic signal. Left turns will be prohibited from Craig Road eastbound to Pond Road northbound. A left-turn lane and a through lane are being added to the westbound approach of East Freehold Road and Pond Road. Currently, it is a single-lane approach. The proposed improvement would provide for a left-turn lane, a through lane, and a shared through/right-turn lane. The southbound approach of Pond Road at Craig/East Freehold Road will be improved to include an exclusive right-turn lane. Currently, it is a single lane approach. The northbound Pond Road ramp to Rt. 9 northbound will be stop controlled.

**COUNTY:** Monmouth

**MUNICIPALITY:** Freehold Twp Manalapan Twp

**MILEPOSTS:** 115.37 - 116.75

**STRUCTURE NO.:** N/A

**LEGISLATIVE DISTRICT:** 11 12

**SPONSOR:** NJDOT

**CIS PROGRAM CATEGORY:** Congestion Relief

**CORE MISSION:** Transportation Services (40)

<b>MPO</b>	<b>Phase</b>	<b>Fund</b>	<b>Amount</b>
NJTPA	CON	NHPP	\$18,675,000

**FY 2014 TRANSPORTATION CAPITAL PROGRAM  
New Jersey Department of Transportation Projects**

<i>Program/Project Name</i>	<i>Item # 79, 79A</i>	<i>Project ID Number: 11418</i>
<b>Route 9, Indian Head Road to Central Ave/Hurley Ave, Pavement</b>		

Pavement Resurfacing MP 94.5 ( north of Indian Head Road in Toms River Township) to MP 101.7 (vicinity of Central / Hurley in Lakewood Township) in Ocean County.  
The object of this improvement is to extent the pavement life, upgrade safety and comply with Federal ADA requirements.

**COUNTY:** Ocean

**MUNICIPALITY:** Toms River Twp Lakewood Twp

**MILEPOSTS:** 94.8 - 101.4

**STRUCTURE NO.:** 1504150 1504151 1504153

**LEGISLATIVE DISTRICT:** 10 30

**SPONSOR:** NJDOT

**CIS PROGRAM CATEGORY:** Road Assets

**CORE MISSION:** State of Good Repair and Safety (10)

<b>MPO</b>	<b>Phase</b>	<b>Fund</b>	<b>Amount</b>
NJTPA	PE	NHPP	\$600,000
NJTPA	DES	NHPP	\$750,000

<i>Program/Project Name</i>	<i>Item # 80</i>	<i>Project ID Number: S0103A</i>
<b>Route 9, Northfield Sidewalk Replacement</b>		

The roadway consists of two 12-foot travel lanes and variable (five to eight foot) width shoulders. Concrete curbing and sidewalks are provided adjacent to the roadway intermittently throughout the project limits. This project will connect the sidewalks and provide missing curbing throughout the project limits. The sidewalks will be constructed from porous pavement.

**COUNTY:** Atlantic

**MUNICIPALITY:** Northfield City

**MILEPOSTS:** 37.06 - 38.14

**STRUCTURE NO.:** N/A

**LEGISLATIVE DISTRICT:** 2

**SPONSOR:** NJDOT

**CIS PROGRAM CATEGORY:** Multimodal Programs

**CORE MISSION:** Transportation Services (40)

<b>MPO</b>	<b>Phase</b>	<b>Fund</b>	<b>Amount</b>
SJTPO	CON	CMAQ	\$1,595,000