


New Jersey Department of Transportation
1035 Parkway Avenue, PO Box 600, Trenton, New Jersey 08625-0600



Baseline Document Change Announcement

ANNOUNCEMENT: BDC23D-04

DATE: October 16, 2023

SUBJECT: Inlet Type B and D Replacement in Existing Concrete Barrier Curb
- Revisions to CD-602-5A and CD-602-5B of the Standard
Construction Details 2016, Roadway

Construction Detail Sheets CD-602-5A and CD-602-5B have been revised to correct and adjust nonstandard pay item references in the original sheets. Other changes have been made to further clarify the intent of the details.

Description of the Changes:

CD-602-5A:

1. Detail renamed to "REPLACE INLET CURB PIECE TYPE B OR D IN EXISTING CONCRETE BARRIER."
2. Direction of traffic added to CD-602-A.1
3. "Concrete" added to inside existing barrier curb in CD-602-5A.1
4. Existing Grate callout added to CD-602-5A.2
5. Sawcut callouts note adjusted in CD-602-5A.2
6. Existing Inlet Wall callout added to CD-602-5A.3
7. "Concrete" added to inside existing barrier curb in CD-602-5A.3
8. Existing Ground level adjusted in CD-602-5A.4
9. "New" inlet casting note changed to "Inlet Casting" in CD-602-5A.4
10. "New Basin Walls" note changed to "Existing Inlet Walls" in CD-602-5A.4
11. "Replacement" title changed to "Reconstruction" in CD-602-5A.4
12. "Slope Towards Grate" callouts added to CD-602-5A.5
13. Added sawcut around inlet curb piece and put callout to explain the actions involved in cutting around the curb piece in CD-602-5A.4
14. Added new notes No. 8 and No. 9 to CD-602-5A.6 to discuss actions involved in cutting around curb piece in item 13 above.
15. Notes revised to adjust all nonstandard line items and reflect changes of the above in CD-602-5A.6

CD-602-5B:


16. Detail renamed to "REPLACE INLET CURB PIECE TYPE B OR D IN EXISTING CONCRETE BARRIER CURB IN NEW CONCRETE SECTION."
17. Direction of traffic added to CD-602-5B.1
18. "Concrete" added to inside existing barrier curb in CD-602-5B.1
19. Existing Grate callout added to CD602-5B.2

20. Sawcut callouts note adjusted in CD-602-5B.2
21. Existing Inlet Wall callout in CD-602-5B.3
22. "Concrete" added on inside existing barrier curb in CD-602-5B.3
23. Existing Ground Level adjusted in CD-602-5B.4
24. "New" inlet casting note changed to "Inlet Casting" in CD-602-5B.4
25. "New Basin Walls" note changed to "Existing Inlet Walls" in CD-602-5B.4
26. "Replacement" title changed to "Reconstruction" in CD-602-5B.4
27. "With Type "B" Concrete" callout removed from CD-602-5B.4
28. "Slope Towards Grage" callouts added to CD-602-5B.5
29. Notes revised to adjust all nonstandard line items and reflect changes of the above in CD-602-5B.6

Implementation Code R (ROUTINE)


Changes must be implemented in all applicable Department projects scheduled for Final Design Submission at least one month after the date of the BDC announcement. This will allow designers to make necessary plan, specifications, and estimate/proposal changes without requiring the need for addenda or postponement of advertisement or receipt of bids.

Recommended By:



Paul F. Schneider
Director
Capital Program Support

Approved By:



Parth Oza, P.E.
Assistant Commissioner
Capital Program Management
and Deputy State Transportation Engineer

PS: NE: MS